

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40324-00-00
Spot: W2E2NENW Sec/Twnshp/Rge: 3-25S-5E
4620 feet from S Section Line, 3245 feet from E Section Line
Lease Name: FRANK ROBINSON WEST Well #: 27
County: BUTLER Total Vertical Depth: 2412 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	2390		
PROD	7	2409		50 SX
SURF	8.625	2210		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 528-0111

Proposed AS PER KCC RULES & REGS
Plugging
Method:

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/03/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2390', QWS MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL & 100# HULLS 2% CC & DISPLACED IN CASING. RIH ON WIRELINE, PERFERATED SQUEEZE HOLES 250'-251' (4 HOLES). RIH WITH TUBING @ 270'. QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL, LAYED DOWN TUBING. SWEDGED INTO 7" QWS MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL 2% CC & 100 # HULLS TO SURFACE. CEMENT CIRCUALTED. 4-3-2018 RIH WITH TUBING @ 240'. QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. TOPPED BACK TO SURFACE WITH 10 SXS.

Perfs:

Top	Bot	Thru	Comments
2409	2412	OH	

INVOICED
APR 20 2018

Remarks: DENIED TA / COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

VJK