

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-129-20544-00-01
 Spot: SENE Sec/Twnshp/Rge: 14-33S-43W
3338 feet from S Section Line, 651 feet from E Section Line
 Lease Name: SANTA FE Well #: 1-14
 County: MORTON Total Vertical Depth: 5010 feet

Operator License No.: 34434
 Op Name: EDISON OPERATING COMPANY LLC
 Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4510	-	2 SX CMT.
CIBP		5010		
L1	4.5	2018		
PROD	5.5	5199	1844	WITH 250 SX CMT
SURF	8.625	1361		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/26/2018 10:00 AM
 Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
 Proposal Rcvd. from: BRIAN J MCCOY Company: EDISON OPERATING Phone: (316) 214-3658

Proposed Plugging Method: PUMP 75 SX CMT WITH 250# HULLS AT 4450'. TOO H WITH TBG. TAG TOC. CUT 5 1/2" CASING BELOW 1350' OR MORE. RUN TBG IN. SPOT 100 SX CMT & 200# HULLS AT 1330'. WOC & TAG. CIRCULATE CMT FROM 350' TO 0'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 02/26/2018 3:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

CIBP @ 5010'. 2/22/18: 1ST PLUG AT 4575' WITH 75 SX CMT & 250# HULLS. 2/23/18: TOC @ 3550'. CUT 5 1/2" CASING OFF AT 1844'. TOO H WITH CASING. 2/26/18: RTIH TO 1418'. 2ND PLUG AT 1418' WITH 100 SX CMT & 200# HULLS. TOO H WITH TBG. TOC @ 950'. 3RD PLUG CIRCULATED 152 SX CMT FROM 352' TO 0'.

Perfs:

Top	Bot	Thru	Comments
5120	5130		
4569	4588		
4146	4150		
3750	3750		
3670	3670		
3656	3661		

INVOICE
APR 20 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
 MAR - 6 2018
 KCC DODGE CITY

Kms
 Form CP-2/3