

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21037-00-00
Spot: SE Sec/Twnshp/Rge: 28-29S-34W
1740 feet from S Section Line, 1370 feet from E Section Line
Lease Name: MLP KOEING Well #: 2-28
County: HASKELL Total Vertical Depth: 5533 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1900		WITH 2 SX CMT
CIBP		5420		WITH 2 SX CMT
CIBP		5533		
PC		2950		WITH 295 SX CMT
PROD 5.5		5646	0	WITH 470 SX CMT
SURF 8.625		1829		WITH 800 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2018 9:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 03/28/2018 2:20 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

CIBP @ 5420' WITH 2 SX CMT. CIBP @ 1900' WITH 2 SX CMT. LOADED HOLE, TESTED OK. RAN BOND LOG. TOC 150' ESTIMATED. RUN TBG TO 1873' & PUMP 30 SX CMT. PULL TO 658' & CIRCULATE TO SURFACE WITH 90 SX CMT TOTAL. TIE ONTO BACKSIDE & PUMP 25 SX CMT. PUMP A TOTAL OF 105 SX CMT ON ANNULUS. PRESSURE TO 250# PUMPING 2-3 BPM.

Perfs:

Top	Bot	Thru	Comments
5512	5518		
5424	5436		

INVOICED
APR 20 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01
RECEIVED
MAR 29 2018
KCC DODGE CITY

Signed [Signature]
(TECHNICIAN)