

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-20336-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 24-30S-10W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: PRICE D Well #: 1  
County: KINGMAN Total Vertical Depth: 4404 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N MARKET STE 1420  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4395	1625	125 SX
SURF	8.625	264		250 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/09/2017 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: SHANNON RAYBERN Company: \_\_\_\_\_ Phone: (620) 793-2672

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/10/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET BRIDGE PLUG AT 4310', LOADED HOLE, BAILED 2 SACKS ON PLUG, PULLED SLIPS, CUT SURFACE OFF 4' BELOW GROUND, RIPPED CASING AT 2410', 2220', 2000', 1840' AND 1625', CAME FREE AT 1625', PULLED TO 1600', PUMEPD 10 GEL, 35 SACKS CEMENT PULLED CASING TO 1000', PUMPED 35 SACKS CEMENT, PULLED CASING TO 320', PUMPED 190 SACKS CLASS A CEMENT TO SURFACE, PULLED REST OF CASING.

Perfs:

Top	Bot	Thru	Comments
4395	4401		

Remarks: QUALITY WELL PROVIDED CEMENT ON THIS JOB. PAST 10 YEAR TA

INVOICED

APR 20 2017

Plugged through: CSG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)