

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21540-00-01
Spot: NWNW Sec/Twnshp/Rge: 31-29S-8W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: CORNELIUS Well #: 1
County: KINGMAN Total Vertical Depth: 4292 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4280	2510	275 SX
SURF	8.625	392		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/26/2018 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: SHANNON RAYBERN Company: _____ Phone: (620) 793-2672

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/06/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP AT 4150', BAILED 2 SACKS CEMENT ON PLUG. LOADED HOLE WITH WATER, CUT SURFACE OFF 4' BELOW GROUND, RIPPED CASING AT 2510' AND PULLED CASING TO 1310'. PUMPED 12 GEL, 50 SX CEMENT, 3% CC, PULLED CASING TO 850', WAITED 2 HOURS, TAGGED CEMENT AT 1050', PUMPED 35 SACKS CEMENT, PULLED CASING TO 440'. PUMEPD 160 SX CEMENT, CIRCULATED TO SURFACE, PULLED REST OF CASING, TOPPED OFF WITH 20 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4206	4216		

INVOICED

Remarks: QUALITY WELL PROVIDED CEMENT ON THIS JOB. NO LEASE.

APR 27 2018

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)

1/2