

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-20909-00-02
Spot: NESWSE Sec/Twnshp/Rge: 8-34S-11E
1258 feet from S Section Line, 1489 feet from E Section Line
Lease Name: SPUR RANCH A Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 2130 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1465		100 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2018 10:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ELMORE'S INC. Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: Run 1" to bottom gel hole spot 5 sacks cement. Pull 1" out perforate at 900' and 500' Run 1" to 900' spot 10 sacks cement pull up to 500' circulate cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 03/27/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report: Ran 1" to 1450' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" into 700' and spotted 7 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 82 sacks of cement were used to plug this well.

Perfs: _____
RECEIVED
KCC DIST #3
APR 17 2018
CHANUTE, KS
DS
INVOICED
APR 27 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC
Plugged through: TBG

District: 03 Signed [Signature]
(TECHNICIAN)