

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21290-00-00Spot: NESWSESec/Twnshp/Rge: 8-34S-11E682 feet from S Section Line, 1467 feet from E Section LineLease Name: SPUR RANCH AWell #: 2County: CHAUTAUQUATotal Vertical Depth: 1450 feetOperator License No.: 5970Op Name: ELMORE, JOHN A. OR PATRICIA R.Address: 776 HWY 99SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1450		0 SX
SURF	7	40		10 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/29/2018 12:00 AMPlug Co. License No.: 32884Plug Co. Name: ELMORE'S, INC.Proposal Rcvd. from: ELMORE'S INC.

Company:

Phone: (620) 249-2519

Proposed Plugging Method: Run 1" to bottom gel hole spot 5 sacks cement Pull 1" out perforate at 900' and 500' run 1" to 900' spot 10 sacks pull 1" up to 500' circulate cement to surface.

Plugging Proposal Received By: DUANE SIMSWitness Type: PARTIALDate/Time Plugging Completed: 03/29/2018 10:00 AMKCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1420' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" into 700' and spotted 7 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 57 sacks of cement were used to plug this well.


RECEIVED
KCC DIST #3
APR 17 2018
CHANUTE, KS

DS

INVOICED
APR 20 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.Plugged through: TBGDistrict: 03

Signed



(TECHNICIAN)