

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23536-00-00
Spot: N2NWSWNW Sec/Twnshp/Rge: 31-13S-12W
1510 feet from N Section Line, 330 feet from W Section Line
Lease Name: SMALL Well #: 1
County: RUSSELL Total Vertical Depth: 3425 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3428	1600	150 SX
SURF	8.625	434		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2018 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Cut casing at 1600' leaving 1825' of 5 1/2" casing in hole.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2018 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/02/2018 - Sanded off perforations and spotted 5 sx of cement on top.
04/03/2018 - Cut casing at 1600'. Pulled casing to 1150' and pumped 125 sx cement w/400 # hulls. Pulled casing to 830' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450' and pumped 50 sx cement. Pulled casing to 230' and pumped 60 sx cement. Circulated cement to the pit. POOH. Topped off casing with 35 sx cement.

GPS: 38.88120 -098.70536

Perfs:

Top	Bot	Thru	Comments
3114	3117		LANSING "G"
3102	3105		LANSING "F"
3048	3052		LANSING "C"

Remarks: QUALITY CEMENTING TICKET # 734

Plugged through: CSG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

4-16-18

APR 09 2018

Form CP-2/3

INVOICED

APR 20 2018