

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23078-00-00
Spot: SWNESESW Sec/Twnshp/Rge: 2-9S-22W
750 feet from S Section Line, 2190 feet from W Section Line
Lease Name: CONNER Well #: 1
County: GRAHAM Total Vertical Depth: 3890 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3887		400 SX
SURF	8.625	222		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2018 10:00 AM
Plug Co. License No.: 35464 Plug Co. Name: NUSS WELL SERVICE, LLC
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 500 # hulls and 15 sx gel.
Perforations: 3816' - 3820' and 3823' - 3826'.
Alt II cwc w/400 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2018 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3800' and pumped 15 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1800' and pumped 180 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 250 psi.

GPS: 39.29433 -099.74598

Perfs:


Top	Bot	Thru	Comments
3823	3826		
3816	3820		

Remarks: QUALITY CEMENT TICKET # 716

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

3-16-18
KCC WICHITA
MAR 16 2018
RECEIVED
INVOICED

APR 20 2018