

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-05784.0000
SE SW NW, Sec. 14, T 20 S, R 12 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5816

Lease Name Buckbee Well # 1

Operator: Gulf Oil Exploration & Prod.
Name & R.R. #2 Box 96-A
Address Hoisington, Ks. 67544

County Barton

Well Total Depth 3435 feet 111.63

Conductor Pipe: Size _____ feet

Surface Casing: Size 8^{5/8} feet 155

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing Co. License Number _____

Address East Highway 40, Hays, Kansas 67601

Company to plug at: Hour: 8:30 AM Day: 15 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Dave Lazure

(company name) Gulf Oil Exploration & Prod. (phone) (316) 653-2576

were: 8^{5/8}"-155' SP CUC w/200 sks. cement, 4^{1/2}" CSG set @ 3435' w/150 sks cement

top of cement back side of 4^{1/2}" CSG 2658', plug back TD 3434' perf's 3399' - 3403'

hole in 4' CSG @ 590', Elev. 1814 - Anh 620' - no pipe recovery. Order 525 sks common

cement, 10 sks flo-cele, 3 sks hulls, run tubing to 3255' and 680' and spot cement,

load annulus between 5^{1/2}" CSG and 8^{5/8}" SP with cement, pump in annulus with pump truck.

Signed *Marion J. Schmidt*
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 PM Day: 15 Month: February Year: 19 84

ACTUAL PLUGGING REPORT Ordered 525 sks common cement, 10 sks flo-cele - 3 sks hulls

spotted with 2^{3/8}" tubing. Spotted 35 sks cement @ 3255' w/1 sk hulls and 2 sks flo-cele,
loaded hole with gel mud.

Spotted 350 sks cement @ 680' w/3 sks flo-cele and w/1 sk hulls mixed in cement cir-

culated, returned on Feb. 16th filled 4^{1/2}" CSG to surface w/20 sks cmt. max. pressure

1000 PSI, pumped in annulus 120 sks cement. w/1 sk hull w/5 sks flo-cele, max pressure

300 PSI (Cemented by Halliburton Cementing)

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1984

CONSERVATION DIVISION 2-27-84
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed *Marion J. Schmidt*
(TECHNICIAN) DOIC

INVOICED

DATE 3-2-84

INV. NO. 0500

2-15

FORM CP-2/3
Rev. 9-82