



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. James J. Simmons guarantees payment of the plugging fee.

Operator's full Name: National Oil Company

Complete Address: 200 W. Douglas, Wichita, Kansas

Lease Name: Tonkin Well No. # 2

Location: NE SE NW Sec. 9 Twp. 20 Rge. 12 (E)(W) W

County: Barton Total Depth 3435 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fred Cameron was instructed to plug the well as follows:

8 5/8" 200' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 180' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Halliburton Cementing Company's pump truck, cementing

to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent