

State of Kansas



15.009.20867.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1975

CONSERVATION DIVISION
Wichita, Kansas

1-14-75

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company has this
date requested permission to plug the following described well:Mr. K. S. Martin guarantees payment of the plugging fee.Operator's full Name: Martin ExplorationsComplete Address: 527 Union Center, Wichita, KansasLease Name: Schartz Well No. # 1Location: SW SE NW Sec. 4 Twp. 20 Rge. 12 (E)(W) WCounty: Barton Total Depth 3423 Oil Well Gas Well Input Well SWD Well D & A XX Lost Hole Mr. Jerb Ogle was instructed to plug the well as follows:8 5/8" csg. 219' Cwc.Circulated hole with heavy mud to 500', set plug, & displaced 40 saxcement thru drill pipe. Mud to 200' & displaced 25 sax cement thrudrill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cementwith Halliburton Cementing Company's pump truck, cementing to baseof cellar.

Very truly yours,

Conservation Division Agent