



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. T. G. Tucker of Kewanee Oil Company has this
date requested permission to plug the following described well:

Mr. Kewanee Oil Company guarantees payment of the plugging fee.

Operator's full Name: Kewanee Oil Company

Complete Address: P. O. Box 2093, Wichita, Kansas 67201

Lease Name: Buckbee Well No. # 3

Location: SW SE NW Sec. 14 Twp. 20 Rge. 12 (E) (W) W

County: Barton Total Depth 3375 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Joe Clarke was instructed to plug the well as follows:

8 5/8" csg. 180' Cwc.

Sanded hole back to 3350' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, plug, &

100 sax cement with Halliburton Cementing Company's pump truck, cementing

from 350' to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent