

State of Kansas



15-009-20947-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

October 5, 1975

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1975

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.Operator's full Name: Kaiser-FrancisComplete Address: 4120 E 51st St., Tulsa, OklahomaLease Name: Wolf "B" Well No. 7Location: C N/2 SE NE Sec. 1 Twp. 20 Rge. 12 (E)(W)XCounty: Barton Total Depth 3369' Oil WellGas Well Input Well SWD Well D & A X Lost HoleMr. Cameron was instructed to plug the well as follows:Fill hole with mud. Push plug to 500' and pump 40 sackscement through drill pipe at 500'. Pump 25 sacks cementthrough drill pipe at 185'. Push plug and 1/2 sack hulls to40' and cap hole with 10 sacks cement. Bridge rathole andcement with 2 sacks cement.

Very truly yours,

Conservation Division Agent