

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26574-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 35-34S-12E
3402 feet from S Section Line, 4917 feet from E Section Line
Lease Name: BOWMAN-FISH Well #: 35-1A
County: CHAUTAUQUA Total Vertical Depth: 2118 feet

Operator License No.: 33066
Op Name: PRAIRIE METHANE GAS PRODUCERS
Address: 399258 W 1330 DR PO BOX 279
DEWEY, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2117		75 SX
SURF	8.625	860		240 SX
T1	2.375	1730		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/24/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ROUNTREE Company: _____ Phone: (918) 534-2322

Proposed Plugging Method: In accordance with KCC inspector.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 02/27/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1980' gelled hole and spotted 7 sack plug. Pulled 1" and perforated casing at 1000', 900', 800', 760' & 275'. Tried to pull casing and couldn't get any of it to come out. Ran 1" back into 1000' and spotted 14 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 118 sacks of cement were used to plug this well. Well was cut off and location restored.

Top	Bot	Thru	Comments
1723	1726		

RECEIVED
KCC DIST # 3
APR 17 2018
CHANUTE, KS
DS
INVOICED

Remarks: WELL WAS PLUGGED DUE TO DENIED CP-111.

APR 27 2018

Plugged through: TBG

District: 03

Signed Duane A Sims
(TECHNICIAN)