

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-185-21694-00-00
 Spot: SENWNWNE Sec/Twnshp/Rge: 28-23S-12W
4814 feet from S Section Line, 2282 feet from E Section Line
 Lease Name: MEYER Well #: 9
 County: STAFFORD Total Vertical Depth: 3824 feet

Operator License No.: 3911
 Op Name: RAMA OPERATING CO., INC.
 Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3770		WITH 2 SX CMT
PROD	5.5	3823	1842	WITH 150 SX CMT
SURF	8.625	718		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2018 8:30 AM
 Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
 Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: CIBP @ 3770' WITH 2 SX CMT. PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 03/15/2018 10:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

SET CIBP @ 3770' WITH 2 SX CMT ON TOP. PRESSURE TEST CASING TO 200 PSI. 1ST PLUG AT 730' WITH 10 SX GEL & 50 SX CMT WITH 100# HULLS. NO RETURNS. LAY DOWN CASING & PICK UP 2 7/8" TBG. TIH TO 750'. TAG CMT WITH SAND LINE AT 1400'. PUMP 50 SX COMMON CMT WITH 3% CC & 100# HULLS. PULL 8 JOINTS OF TBG. WAIT ON CMT 1 HOUR. TAGGED AT 1400' AGAIN. TIH WITH TBG TO 750'. PUMP 50 SX COMMON CMT WITH 6% CC, 100# HULLS & 50# CELLO-FLAKE. PULLED 8 JOINTS TBG & WAIT ON CMT 1 HOUR. TAGGED CMT AT 1000'. TIH WITH TBG TO 750' & PUMP 50 SX CMT WITH 6% CC, 100# HULLS & 50# CELLO-FLAKE. PULL TBG & SDON. 3/15/18: TAG CMT AT 500'. TIH WITH TBG TO 250' & PUMP 50 SX CMT. PULL TBG TO 30' & PUMP 20 SX CMT TO FILL HOLE.

Top	Bot	Thru	Comments
3822	3824		

Remarks: USED 60/40 POZMIX & COMMON CEMENT BY BASIC ENERGY SERVICES.

Plugged through: TBG

INVOICED

APR 27 2018

District: 01

Signed *Ken Scofield*
 (TECHNICIAN)

RECEIVED
 MAR 20 2018
 KCC DODGE CITY