

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22297-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 30-26S-12W  
2318 feet from S Section Line, 1075 feet from E Section Line  
Lease Name: LUNDGRIN Well #: 1-30  
County: PRATT Total Vertical Depth: 4340 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4275	2390	WITH 225 SX CMT
SURF	8.625	349		WITH 350 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2018 11:30 AM  
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.  
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: PUMP BOTTOM WITH 150 SX CMT. TAG TOC. PLUG AT 780' WITH 12 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2018 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RUN TBG INTO 4240' & SPOT 150 SX CMT WITH 500# HULLS. LET CMT SET. TAG TOC @ 2900'. 1ST PLUG AT 790' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3852	3856		
3753	3757		
3722	3726		
3528	3534		
3063	3852		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

INVOICED

APR 27 2018

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
MAR 20 2018  
KCC DODGE CITY

*MD*

SA