

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-147-00638-00-02  
Spot: NWNW Sec/Twnshp/Rge: 25-4S-20W  
660 feet from N Section Line, 660 feet from W Section Line  
Lease Name: LYNCH OWWO Well #: 2  
County: PHILLIPS Total Vertical Depth: 3825 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3509		125 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2018 12:30 PM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Production perforations: 3218' - 3825'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2018 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1520' and 950'. Ran tubing to 3180' and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 2220' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1260' and  
pumped 100 sx cement to circulate cement to surface. Pulled tubing and topped off 5 1/2"  
casing with 20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 50 sx cement. Shut  
in pressure 200 #'s.

GPS: 39.68171N -099.53220W

Perfs:

Top	Bot	Thru	Comments
3509	3825		
3351	3355		
3331	3335		
3314	3317		
3218	3222		

Remarks: GLOBAL CEMENTING TICKET # 3314

Plugged through: TBG

INVOICED

APR 27 2018

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 09 2018

APR 16 2018

4-16-18

CONSERVATION DIVISION  
WICHITA, KS