

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22622-00-01
Spot: SESENE Sec/Twnshp/Rge: 15-6S-23W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCHUCK 15AD Well #: 1
County: GRAHAM Total Vertical Depth: 3830 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3828		125 SX
SURF	8.6252	246		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2018 9:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3598' - 3600', 3613' - 3618' and 3682' - 3683'.
Port Collar set at 2050' w/310 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2018 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3570' and pumped 95 sx cement w/250 # hulls. Pulled tubing to 2770' and pumped 95 sx cement w/100 # hulls. Pulled tubing to 1870' and pumped 175 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.53278 -099.86449

Perfs:

Top	Bot	Thru	Comments
3682	3683		SPF - EXISTING
3614	3618		SPF - EXISTING
3613	3618		
3598	3600		SPF - NEW

Remarks: GLOBAL CEMENT TICKET # 3309

Plugged through: TBG

INVOICED

APR 27 2018

District: 04

Signed

Marvin Mills
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

MAR 26 2018

MAR 26 2018

APR 16 2018

4-16-18

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS