

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21421-00-00
Spot: S2NWNSE Sec/Twnshp/Rge: 2-12S-25W
2200 feet from S Section Line, 990 feet from E Section Line
Lease Name: HLADEK "P" Well #: 4
County: TREGO Total Vertical Depth: 4180 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4174		175 SX
SURF	8.625	243		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/13/2018 12:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 4076' - 4078' and 4095' - 4098'.
Tubing and rods stuck in hole at 3090'. Got hold of one time with overshot. Pulled 50,000 and couldn't get loose. Tried later and couldn't get back on tubing.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2018 7:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3090' and pumped 100 sx cement. Pulled tubing to 2150' and pumped 215 sx cement. Good circulation of cement. Tied on to backside and squeezed with 50 sx cement. 03/27/2018 - Topped off casing with 44 sx redi mix cement.

GPS: 39.03672 -100.05915

Perfs:

Top	Bot	Thru	Comments
4095	4098		
4076	4078		

Remarks: GLOBAL CEMENT TICKET # 3290

Plugged through: TBG

INVOICED

APR 27 2018

District: 04

Signed _____
Received _____
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 16 2018

4-16-18

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAR 26 2018