

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22169-00-00
Spot: W2SEWSE Sec/Twnshp/Rge: 19-12S-21W
1650 feet from S Section Line, 1800 feet from E Section Line
Lease Name: DEUTSCHER A Well #: 2
County: TREGO Total Vertical Depth: 4040 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4038		120 SX
SURF	8.625	202		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2018 11:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3584' - 3588', 3726' - 3729' and 3997' - 4000'.
CIBP set at 3966'.
Port Collar set at 1698' w/430 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2018 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3720' and pumped 95 sx cement w/250 # hulls. Pulled tubing to 2952' and pumped 95 sx cement w/100 # hulls. Pulled tubing to 2024' and pumped 175 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 200 psi.

GPS: 38.99163 -099.69321

Perfs:

Top	Bot	Thru	Comments
3997	4000		
3726	3729		
3584	3588		

Remarks: GLOBAL CEMENT TICKET # 3149

Plugged through: TBG

INVOICED

APR 27 2018

District: 04

Signed _____
Received _____
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

4-16-18

Form CP-2/3

MAR 26 2018