

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22078-00-00
Spot: SESESWNE Sec/Twnshp/Rge: 31-11S-19W
2790 feet from S Section Line, 1532 feet from E Section Line
Lease Name: DALE SOLOMON B Well #: 1-31
County: ELLIS Total Vertical Depth: 3762 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3760		200 SX
SURF	8.625	173		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2018 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
03/07/2018 - Tubing parted in hole at 890'. Tubing and packer in hole.
03/09/2018 - Recovered the rest of tubing above packer. Packer in hole at 3630'.
PBSD: 3720'.
Perforations: 3703' - 3710', 3714' - 3718' Arbuckle.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2018 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1850', 1507' and 830'. Express Well Service ran in hole with tubing to 3600' and pumped 30 sx neat cement followed by 145 sx cement w/200 # hulls mixed in. Pulled tubing to 1850' and pumped 150 sx cement w/400 # hulls mixed in to circulate cement to pit area. Pulled tubing. Rigged to 5 1/2" casing with a swage and pumped 30 sx cement with 300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" surface casing and pumped 35 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

GPS: 39.05273 -099.46902

Perfs:

Top	Bot	Thru	Comments
3714	3718		
3703	3710		

Remarks: GLOBAL CEMENTING CO. TICKET # 3146

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

3-16-18
KCC WICHITA

MAR 16 2018

RECEIVED

INVOICED

APR 27 2018

MAR 12 2018