

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-27749-00-00
Spot: NENENESE Sec/Twnshp/Rge: 8-27S-20E
2475 feet from S Section Line, 165 feet from E Section Line
Lease Name: LINDBERG Well #: L-81
County: NEOSHO Total Vertical Depth: 900 feet

Operator License No.: 34897
Op Name: SCZ RESOURCES, LLC
Address: 8614 CEDARSPUR DR.
HOUSTON, TX 77055

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	25		9 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2014 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: Run cement string to TD and pump full.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 09/30/2014 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1 inch cement string was washed to 900 ft and the hole gelled. 14 sacks of cement were then spotted at TD. The cement string was pulled to 500 ft and 14 sacks of cement spotted. The cement string was pulled to 225 ft and the well filled to surface with 45 sacks of cement. A total of 73 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST # 3
MAR 09 2018
CHANUTE, KS

AD

Remarks:

Plugged through: OH

INVOICED
APR 27 2018

District: 03

Signed Alan Dunning
(TECHNICIAN)