

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26558-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 9-34S-12E
1109 feet from S Section Line, 1167 feet from E Section Line
Lease Name: OSCAR Well #: 1A
County: CHAUTAUQUA Total Vertical Depth: 1679 feet

Operator License No.: 35116
Op Name: SM OIL & GAS, INC.
Address: PO BOX 189
SKIATOOK, OK 74070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1630		
PROD	4.5	1650		220 SX
SURF	8.625	40		12 SX
T1	2.375	1200		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/16/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOEL POTTS Company: _____ Phone: (918) 977-1178

Proposed Plugging Method: Plug in accordance with KCC rules and regulations.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 03/16/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1254' gelled hole and spotted 10 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 43 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1630			
1262	1274		

RECEIVED
KCC DIST # 3
APR 17 2018
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED PER DENIED CP-111 FOR LACK OF LEASE ON WELL.


Plugged through: TBG

INVOICED

APR 27 2018

District: 03

Signed



(TECHNICIAN)