

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-22800-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 26-29S-4E  
1050 feet from S Section Line, 4314 feet from E Section Line  
Lease Name: MUDDY CREEK SW UNIT Well #: 10  
County: BUTLER Total Vertical Depth: 2950 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2780		
PROD	5.5	2950	1520	100 SX
SURF	8.625	260		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2018 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALLEN KEARNS Company: \_\_\_\_\_ Phone: (620) 222-4068

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/10/2018 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIBP SET AT 2780', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1520', LAYED DOWN CASING @ 321', QWS SWEDGED INTO CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN CASING. PULLED OUT OF HOLE WITH 1520' 48 JOINTS 5 1/2" CASING. CEMENT CIRCULATED. TOPPED BACK TO SURFACE WITH 10 SXS.

Perfs:

Top	Bot	Thru	Comments
2835	2858	CSG	

Remarks:

Plugged through: TBG

INVOICED

APR 27 2018

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

1/2