

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-22220-00-00  
Spot: NENESESE Sec/Twnshp/Rge: 27-29S-4E  
1045 feet from S Section Line, 96 feet from E Section Line  
Lease Name: MUDDY CREEK SOUTHWEST Well #: 7  
County: BUTLER Total Vertical Depth: 2939 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2795		
PROD	5.5	2940	1530	100 SX
SURF	8.625	229		115 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2018 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALLEN KEARNS Company: \_\_\_\_\_ Phone: (620) 222-4068

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/11/2018 9:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

CIBP SET @ 2795', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1630'. LAYED CASING DOWN @ 315', QWS SWEDGED INTO CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN CASING. PULLED OUT OF HOLE WITH 1630', 46 JOINTS 5 1/2" CASING. CEMENT CIRCULATED.

Top	Bot	Thru	Comments
2844	2847	CSG	

Remarks:

Plugged through: TBG

INVOICED  
APR 27 2018

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

1/4