

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22336-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 35-29S-4E
4440 feet from S Section Line, 5086 feet from E Section Line
Lease Name: MUDDY CREEK SOUTHWEST Well #: 2-B
County: BUTLER Total Vertical Depth: 2909 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY SUITE 2
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2760		
PROD	5.5	2909	1512	100 SX
SURF	8.625	260		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2018 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN KEARNS Company: _____ Phone: (620) 222-4068

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/10/2018 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIBP SET @ 2760', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1512', LAYED DOWN CASING @ 305', QWS SWEDGED INTO CASING, ESTABLISHED CIRCULATION, MIXED AND PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN CASING, PULLED OUT OF HOLE WITH 1,510' 47 JOINTS 5 1/2" CASING. CEMENT CIRCULATED. TOPPED BACK TO SURFACE WITH 5 SXS.

Perfs:

Top	Bot	Thru	Comments
2811	2824	CSG	

Remarks:

Plugged through: TBG

INVOICED

APR 27 2018

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

✓