

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-173-01926-00-00
Spot: SESWNE Sec/Twnshp/Rge: 4-26S-2E
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: FEIK Well #: 3
County: SEDGWICK Total Vertical Depth: 2898 feet

Operator License No.: 33215
Op Name: TAYLOR, ROBERT W. DBA TAYLOR OI
Address: PO BOX 894
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2888		50 SX
SURF	8.625	95		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2017 11:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: ROBERT TAYLOR Company: TAYLOR OIL Phone: (316) 321-0910

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 10/09/2017 3:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

CIBP SET @ 2839' CAPPED WITH 5 SX. TAGGED TOP OF BOTTOM PLUG AT 2772'. OPERATOR HAD PERFORATED 5.5" AT 150' BEFORE CLEARING THIS WITH DISTRICT OFFICE AND OPERATOR GOT AN EXCEPTION FROM DISTRICT 2 SUPERVISOR AND THIS WAS OK'D OVER THE NORMAL 250' REQUIRED. OPERATOR RAN BACK IN WITH TUBING TO 150' AND CIRCULATED 60/40 POS MIX W/4% GEL AND 1% OF CC TO SURFACE. CEMENT STOOD FULL AND OPERATOR CAME BACK AND CUT OFF BELOW GROWN LEVEL. CONSOLIDATED CEMENT TICKET #54736.

INVOICED
APR 27 2019

Remarks: NOTE: WELL WAS PLUGGED DUE TO HIGH FLUID LEVEL AND DENIED TA APPLICATION

Plugged through: TBG

District: 02

Signed *Daniel Fox*
(TECHNICIAN)

✓