

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23420-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 28-34S-11W
2078 feet from S Section Line, 3205 feet from E Section Line
Lease Name: L B DIEL Well #: 1-28
County: BARBER Total Vertical Depth: 5140 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4670		WITH 2 SX CMT
PROD	5.5	4887	3406	WITH 125 SX CMT
SURF	10.75	288		WITH 250 SX CMT

Well Type: OIL UIC Docket No.: _____ Date/Time to Plug: 04/05/2018 12:45 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY, INC. Phone: (316) 218-5853

Proposed Plugging Method: SET CIBP @ 4675' WITH 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2018 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4670' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 580' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT. TOP OFF WELL WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4735	4746		
4725	4746		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

INVOICED

APR 27 2018

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
APR - 6 2018
KCC DODGE CITY