

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23517-00-00
Spot: W2E2E2SW Sec/Twnshp/Rge: 28-34S-11W
1320 feet from S Section Line, 3135 feet from E Section Line
Lease Name: LB DIEL Well #: 3-28
County: BARBER Total Vertical Depth: 4881 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4680 | | WITH 2 SX CMT |
| PROD | 5.5 | 4865 | 3484 | WITH 100 SX CMT |
| SURF | 8.625 | 223 | | WITH 190 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY Phone: (316) 218-5853

Proposed Plugging Method: CIBP @ 4680' WITH 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE
Date/Time Plugging Completed: 03/26/2018 9:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4680' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4734 | 4759 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

INVOICED
APR 27 2018

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

SA

RECEIVED
MAR 28 2018
KCC DODGE CITY