

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23303-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 18-34S-10W
495 feet from N Section Line, 495 feet from W Section Line
Lease Name: FOSTER/KERN Well #: 1-18
County: BARBER Total Vertical Depth: 4800 feet

Operator License No.: <u>5822</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>VAL ENERGY, INC.</u>	CIBP		4600		WITH 2 SX CMT
Address: <u>125 N MARKET ST STE 1110</u>	PROD	5.5	4784	3697	WITH 125 SX CMT
<u>WICHITA, KS 67202</u>	SURF	8.625	241		WITH 185 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/22/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY Phone: (316) 218-5853

Proposed Plugging Method: CIBP @ 4600' WITH 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE
Date/Time Plugging Completed: 03/22/2018 10:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4600' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4648	4670		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICING & CEMENTING.

Plugged through: CSG

District: 01

Signed [Signature]
SA (TECHNICIAN)

RECEIVED
MAR 28 2018
KCC DODGE CITY