

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23878-00-00  
Spot: SEWNENESE Sec/Twnshp/Rge: 9-31S-13W  
2200 feet from S Section Line, 935 feet from E Section Line  
Lease Name: NITTLER Well #: 1-9  
County: BARBER Total Vertical Depth: 4460 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 125 N MARKET ST STE 1110  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4172		WITH 2 SX CMT
PROD	5.5	4422	2512	WITH 100 SX CMT
SURF	8.625	224		WITH 190 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/28/2018 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: DEON HOWARD Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: CIBP @ 4170' WITH 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 255' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE  
Date/Time Plugging Completed: 03/28/2018 3:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4172' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 607' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 50 SX CMT. 3RD PLUG AT 40' TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4260	4270		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICING & CEMENTING.

Plugged through: CSG

INVOICED  
APR 27 2018

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
MAR 29 2018  
KCC DODGE CITY

SA