

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-20715-00-00  
Spot: NESWNWSE Sec/Twnshp/Rge: 1-11S-34W  
1900 feet from S Section Line, 2240 feet from E Section Line  
Lease Name: THRASHER V Well #: 1  
County: LOGAN Total Vertical Depth: 4800 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4792		235 SX
SURF	8.625	265		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2018 9:00 AM  
Plug Co. License No.: 35052 Plug Co. Name: HUSKER ENERGY SERVICES, INC.  
Proposal Rcvd. from: DAVID VAN DIKE Company: VESS OIL CORPORATION DBA Phone: (316) 682-1537

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
8 5/8" surface casing set at 265' w/170 sx cement.  
4 1/2" production casing set at 4792' w/235 sx cement.  
TD 4800'. PBTD 4757'.  
Perforations: 4311' - 4314', 4358' - 4362' and 4669' - 4672'.  
Stage collar set at 2680' w/365 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/23/2018 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4260' and pumped 100 sx cement w/400 # hulls. Pulled tubing to 3150' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1600' and pumped 120 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 15 sx cement.

GPS: 39.12435N -101.04240W

Perfs:

Top	Bot	Thru	Comments
4669	4672		SPF
4358	4362		SPF
4311	4314		SPF

*3-16-18*  
KCC WICHITA  
MAR 16 2018  
RECEIVED

Remarks: HUSKER ENERGY SERVICES INC. PULLING UNIT. BASIC ENERGY SERVICES CEMENT TICKET # 16,186

Plugged through: TBG

INVOICED

APR 27 2018

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

FEB. 28 2018