

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-20926-00-00  
Spot: SWNENESW Sec/Twnshp/Rge: 24-21S-25W  
2010 feet from S Section Line, 3275 feet from E Section Line  
Lease Name: WITMAN C Well #: 1  
County: HODGEMAN Total Vertical Depth: 4495 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 4420       |             | WITH 2 SX CMT   |
| PROD   | 4.5   | 4472       | 0           | WITH 100 SX CMT |
| SURF   | 8.625 | 408        |             | WITH 275 SX CNT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2018 8:30 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: HUNTER HEMBREE Company: VESS OIL Phone: (316) 682-1537

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. PERFORATE AT 1600' & PUMP 80 SX CMT, 40 SX WITHOUT HULLS & 40 SX WITH HULLS. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/12/2018 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

SET CIBP @ 4420' WITH 2 SX CMT. PERFORATED AT 1600' & PUMPED 40 SX CMT THEN 40 SX CMT WITH 150# HULLS. PERFORATE AT 600' & PUMPED 150 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 300# & HELD.

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4472 | 4495 |      |          |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: CSG

INVOICE

APR 27 2018

District: 01

Signed

Michael Maier  
(TECHNICIAN)

RECEIVED  
FEB 16 2018  
KCC DODGE CITY

MP

SA

Form CP-2/3