

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30716-00-00
Spot: NWSESE Sec/Twnshp/Rge: 30-33S-16E
1037 feet from S Section Line, 810 feet from E Section Line
Lease Name: HIGHT Well #: 16-30
County: MONTGOMERY Total Vertical Depth: 1229 feet

Operator License No.: 32353
Op Name: GATEWAY RESOURCES U.S.A., INC.
Address: 1821 ARBOR DR
BARTLESVILLE, OK 74006

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1224		140 SX
SURF	8.625	22		5 SX
T1	2.375	1200		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/30/2018 12:00 AM
Plug Co. License No.: 33739 Plug Co. Name: SEK ENERGY, LLC
Proposal Rcvd. from: RICHARD BOONE Company: _____ Phone: (918) 695-8969

Proposed Cement plug the perfs. 50 ft plug at half way point. Plug 225 ft to surface.
Plugging Method:

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" tubing to 1092' gelled hole and spotted 6 sack plug. Pulled up to 935' and spotted 6 sack plug. Pulled up to 465' and spotted 6 sack plug. Pulled up to 217' and tried to circulate cement to surface with 28 sacks. Could not get cement to circulate. Pulled 2". Came back the next day and tagged cement at 350'. Circulated cement to surface. Pulled 2" and topped well off. A total of 62 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1185	1188		
1046	1048		
1042	1048		
932	935		

RECEIVED
KCC DIST #3
APR 17 2018
CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

APR 24 2018