

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-30637-00-00
Spot: NENENW Sec/Twnshp/Rge: 26-34S-14E
4931 feet from S Section Line, 3169 feet from E Section Line
Lease Name: BRAKE Well #: 26-2
County: MONTGOMERY Total Vertical Depth: 1657 feet

Operator License No.: 32353
Op Name: GATEWAY RESOURCES U.S.A., INC.
Address: 1821 ARBOR DR
BARTLESVILLE, OK 74006

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1664		200 SX
SURF	8.625	20		5 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/28/2018 10:00 AM
Plug Co. License No.: 33739 Plug Co. Name: SEK ENERGY, LLC
Proposal Rcvd. from: RICHARD BOONE Company: _____ Phone: (918) 695-8969

Proposed Plugging Method: Cement plug the perms. 50 ft plug at half way point to surface. Plug 225 ft to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2018 8:30 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 2" to 1562' and hit what we think was a bridge plug. Gelled hole and spotted 7 sacks of cement. Pulled up to 1100' and spotted 6 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. Ran 1" down backside and tagged cement at 20'. Circulated cement to surface. Pulled 1" and topped off. A total of 37 sacks of cement were used to plug this well


Top	Bot	Thru	Comments
1579	1582		

RECEIVED
KCC DIST # 3
APR 17 2018
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)

INVOICED
APR 25 2018