

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21637-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 12-27S-6W
2265 feet from S Section Line, 2213 feet from E Section Line
Lease Name: PRAIRIE GEM (GOERING) Well #: 1
County: KINGMAN Total Vertical Depth: 2913 feet

Operator License No.: 30331
Op Name: GOERING, MARVIN
Address: 10758 NE 40TH ST
MURDOCK, KS 67111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2841		40 SXS CMT
SURF	7	228		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/07/2018 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (316) 772-6646

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2018 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 2710' & CAPPED WITH 2 SKS CEMENT. RIPPED CASING AT 2610', 2430'. CAME LOOSE AT 2300'. PULLED CASING TO 500' & SPOTTED 35 SX CEMENT. PULLED CASING TO 270' & CIRCUALTED CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2763	2842		

INVOICED

Remarks: QUALITY WELL SERVICE, COMMON CEMENT. DENIED TA

APR 25 2018

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)