

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20648-00-00
Spot: N2SW Sec/Twnshp/Rge: 13-31S-42W
1988 feet from S Section Line, 3956 feet from E Section Line
Lease Name: GRIMWOOD Well #: 2-13
County: MORTON Total Vertical Depth: 5300 feet

Operator License No.: 35161
Op Name: HIGH PLAINS PRODUCTION, LLC
Address: PO BOX 1548
MURRAY, KY 42071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5290	1515	WITH 250 SX CMT
SURF	8.6252	1491		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/27/2018 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: ADAM IRSIK Company: _____ Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/27/2018 1:30 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

2/26/18; TBG STUCK AT 1578'. CUT TBG OFF AT 1560'. TOO H. CUT 4 1/2" CASING OFF AT 1515' THEN TOO H. 2/27/18: RTIH YO 1542'. 1ST PLUG AT 1542' WITH 100 SX CMT 3% CC HOT PLUG, TOC @ 1413'. LOADED CASING WITH WATER & IT HELD WITH WATER. RTIH TO 598'. 2ND PLUG CIRCULATE 65 SX CMT FROM 598' TO SURFACE. TOO H WITH TBG. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5156	5162		
5096	5108		

INVOICED

APR 25 2018

Remarks: USED COMMON CLASS A CEMENT & 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAR - 5 2018
KCC DODGE CITY

[Signature]
Form CP-2/3