

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-21913-00-00  
Spot: NWNWNWNE Sec/Twnshp/Rge: 35-23S-33W  
5132 feet from S Section Line, 2584 feet from E Section Line  
Lease Name: SCHWEER Well #: 1-35  
County: FINNEY Total Vertical Depth: 2636 feet

Operator License No.: 35161  
Op Name: HIGH PLAINS PRODUCTION, LLC  
Address: PO BOX 1548  
MURRAY, KY 42071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2630	0	WITH 550 SX CMT
SURF	8.625	425		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2018 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: WALT DINKEL Company: QES Phone: (620) 287-3501

Proposed Plugging Method: FILL 5 1/2" CASING WITH CMT USING 250# HULLS & 275 SX CMT. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2018 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL THE 5 1/2" CASING WITH CMT FROM 2603' TO 0' USING 250# HULLS & 250 SX CMT. PRESSURE CASING TO 400#. HOLDING. PUMP 20 SX CMT DOWN THE ANNULUS & PRESSURE TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2595	2603		
2573	2581		

INVOICED  
APR 25 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

District: 01

Signed

*Ken Jehlik*  
SA

(TECHNICIAN)

RECEIVED  
FEB 20 2018  
KCC DOCUMENTS