

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01495-00-00
Spot: SWNWNWNW Sec/Township/Rge: 10-26S-8E
648 feet from N Section Line, 200 feet from W Section Line
Lease Name: RICE Well #: 37-D
County: GREENWOOD Total Vertical Depth: 2560 feet

Operator License No.: 5697
Op Name: JACKSON BROTHERS, L.L.C.
Address: 116 E 3RD ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2559		100 SX
SURF	8.625	89		50 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/09/2018 12:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Revd. from: ROSCOE G. JACKSON II Company: Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-ft. cement plug inside 5.500" casing at 2400-2350 ft. 2. 50-ft. cement plug inside and outside 5.500" at 1250-1200 ft. 3. Continuous cement plug inside and outside 5.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 04/11/2018 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

spotted 7 sxs cement @ 2350' w/dump baler, ran tubing to 1200', pumped 20 sxs cement, pulled tubing to 250', pumped 55 sxs cement to surface, gel spaceers between cement plugs.

Top	Bot	Thru	Comments
2418	2436		

RECEIVED
KCC DIST # 3
APR 16 2018
CHANUTE, KS

MT

INVOICED

Remarks:

APR 25 2018

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)



Camp Ellex, K²

"Thank You"

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.