

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-22182-00-00  
Spot: S2S2NENE Sec/Twnshp/Rge: 10-26S-8E  
1155 feet from N Section Line, 660 feet from E Section Line  
Lease Name: RICE Well #: 8  
County: GREENWOOD Total Vertical Depth: 2540 feet

Operator License No.: 5697  
Op Name: JACKSON BROTHERS, L.L.C.  
Address: 116 E 3RD ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2495	1075	75 SX
SURF	8.625	106		66 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/29/2018 12:00 AM  
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC  
Proposal Revd. from: ROSCOE G. JACKSON II Company: \_\_\_\_\_ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-ft. cement plug inside 4.500" casing at 2400-2350 ft. 2. 50-ft. cement plug inside and outside 4.500" at 1150-1100 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/02/2018 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran dump mbaler spotted 7 sxs cement @ 2400', shot casing off @ 1075', pumped 20 sxs cement, pulled casing to 250', pumped 125 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2423	2450		

RECEIVED  
KCC DIST # 3  
APR 09 2018  
CHANUTE, KS

MH

INVOICED

Remarks:

Plugged through: CSG

District: 03

Signed

  
(TECHNICIAN)

3 APRIL 2018 PAID BY JBLLC CHECK #9221 = \$3,696.16

810 E 7TH  
PO Box 92  
EUREKA, KS 67045  
(620) 583-5561



15073-22182 00 00  
Cement or Acid Field Report  
Ticket No. **3818**  
Foreman Kevin McCoy  
Camp EUREKA

Received 3 April 2018

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
4-2-18	1008	Rice # 8	10	26S	8E	Gw	Ks	
Customer <u>JACKSON BROTHERS LLC</u>			Safety Meeting KM DG RL SM		Unit #	Driver	Unit #	Driver
Mailing Address <u>116 E. 3rd</u>					<u>102</u>	<u>KICK L.</u>		
City <u>EUREKA</u>			State <u>Ks</u>		<u>114</u>	<u>DAVE G.</u>		
Zip Code <u>67045</u>					<u>145</u>	<u>STEVE M.</u>		

Job Type P.T.A. old well Hole Depth \_\_\_\_\_ Slurry Vol. 36 BBL Tubing \_\_\_\_\_  
 Casing Depth \_\_\_\_\_ Hole Size 7 7/8" Slurry Wt. 14.1# Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting: Bottom Plug Set By Long DR19 Co. @ 2390' w/ Cable Tool. Shot casing off @ 1075'. Rig up to 4 1/2 casing. Pump 300# Gel w/ 15k Hulls. Spot 20 SKs 60/40 Pozmix Cement w/ 4% Gel @ 1075'. Pull 4 1/2 up to 250'. Spot Solid Cement Plug from 250' to surface. Pull 4 1/2. Top of well w/ Cement. Top Plug = 125 SKs Cement. Well standing full of cement. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	10	Mileage	3.95	39.50
C 205	145 SKs	60/40 Pozmix Cement	12.75	1848.75
C 206	500 "	Gel 4%	.20 "	100.00
C 206	300 "	Gel	.20 "	60.00
C 214	40 "	Hulls	.45 "	18.00
C 108A	6.24 Tons	Ton Mileage	M/c	345.00
C 113	5 Hrs	80 BBL VAC TRUCK	85.00	425.00
C 224	3300 gals	City water	10.00/1000	33.00
			Sub Total	3619.25
			Less 5%	194.53
			Sales Tax	271.44
			Total	3696.16

THANK YOU

Authorization Roscoe Jackson II Title CO-MANAGER Total 3696.16

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.