

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-20818-00-00  
Spot: NWNWSENW Sec/Twnshp/Rge: 29-26S-8E  
3670 feet from S Section Line, 3735 feet from E Section Line  
Lease Name: DRUMM Well #: 15  
County: BUTLER Total Vertical Depth: 2762 feet

Operator License No.: 35164  
Op Name: JIM SNYDER, INC.  
Address: PO BOX 109  
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2760		100 SX
SURF	8.628	210		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2018 8:00 AM  
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.  
Proposal Revd. from: JOEL SNYDER Company: \_\_\_\_\_ Phone: (620) 344-6042

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP SET @ 2600' W/5 SXS PERF & CIRCULATE 260'-0-

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/09/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2703', TAGGED TD @ 2718'. SNYDER INC. MIXED & PUMPED 5 BBLs GEL PLUG & DISPLACED IN CASING. POOH W/TUBING @ 2641'. SNYDER INC. MIXED & PUMPED 7 SXS CLASS A COMMON & DEPLACED IN CASING. LAYED DOWN 11 JOINTS TUBING. 2-16-18 TAGGED CEMENT @ 2295'. RIH W/TUBING @ 2295', SNYDER INC. MIXED AND PUMPED 8 SXS CLASS A COMMON & DISPLACED IN CASING. 2-27-18 TAGGED CEMENT @ 1200'. CUT CASING @ 260', SNYDER LAYED DOWN 260' 5 1/2" CASING. BAILED HOLE DRY @ 260', CMC POURED 90 SX SLURRY MIX TO SURFACE. POURED 256'-0". CMC TICKET #400048938.

Perfs:

Top	Bot	Thru	Comments
2655	2730	OH	

Remarks: COMPLIANCE / DENIED TA / COMPLIANCE LIST

Plugged through: TBG

INVOICED  
APR 25 2018

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

JJK