

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20642-00-00
Spot: NWNENW Sec/Twnshp/Rge: 29-26S-8E
5106 feet from S Section Line, 3690 feet from E Section Line
Lease Name: DRUMM Well #: 11
County: BUTLER Total Vertical Depth: 2765 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2660		
PROD	5.5	2764		100 SX CMT
SURF	8.625	200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2018 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Revd. from: JOEL SNYEDER Company: _____ Phone: (620) 344-6042

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 2550' W/5 SXS. PULL PIPE AND CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/09/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING & TAGGED BOTTOM @ 2588'. PULLED TUBING @ 2576'. SNYDER INC. MIXED & PUMPED 5 BBL GEL PLUG, & MIXED AND PUMPED 7 SXS CLASS A CEMENT & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2503'. CUT CASING @ 260', LAYED DOWN 260' 5 1/2" CASING. BAILED HOLE DRY @ 260', CMC POURED 90 SXS SLURRY MIX TO SURFACE. POURED 256'-0'. CMC TICKET # 400048938.

Perfs:

Top	Bot	Thru	Comments
2698	2717	CSG	
2602	2607	CSG	

Remarks: COMPLIANCE LIST/ DENIED TA'S

Plugged through: TBG

INVOICED
APR 25 2018

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

JK