

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40099-00-00
Spot: NENENW Sec/Twnshp/Rge: 6-34S-12E
4814 feet from S Section Line, 2677 feet from E Section Line
Lease Name: PERU FARM Well #: 71
County: CHAUTAUQUA Total Vertical Depth: 1139 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	975		0 SX
SURF	10.75	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1112' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 600' and 275'. Ran 1" back into 600' and spotted 20 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 180 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
918	932		

RECEIVED
KCC DIST # 3
APR 04 2018
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC INVOICED
Plugged through: TBG APR 25 2018

District: 03 Signed [Signature]
(TECHNICIAN)