

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00842-00-00  
Spot: SW Sec/Twnshp/Rge: 10-24S-32W  
1327 feet from S Section Line, 3993 feet from E Section Line  
Lease Name: MAYO A Well #: 1  
County: FINNEY Total Vertical Depth: 2580 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, LLC  
Address: 600 TRAVIS STE 1400  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2474		WITH 2 CMT
PROD	5.5	2574	0	WITH 900 SX CMT
SURF	8.625	926		WITH 525 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/26/2018 2:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: WES LOGAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: CIBP @ 2474'. 12 BBL SPACER 2420'-1900'. 35 SX CMT 1900'-1600'. 12 BBL SPACER 1600'-1100'. 110 SX CMT 1100'-0'. FILL ANNULUS

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/26/2018 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2474' WITH 2 SX CMT. WIRELINE FLUID LEVEL = 2420'. PUMP 12 BBL SPACER FROM 2420'-1930'. PUMP 35 SX CMT FROM 1930'-1600'. PUMP 10 BBL SPACER FROM 1600'-1200'. SHUT DOWN. BLED OFF AIR. PUMP 140 SX CMT FROM 1200'-0'. ATTEMPT TO PUMP DOWN THE ANNULUS. COULD NOT. FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2545	2554		
2540	2542		
2504	2532		


Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

INVOICED  
APR 26 7 03 AM

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
MAR - 6 2018  
KCC DODGE CITY