

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00847-00-00
Spot: NENESWNW Sec/Twnshp/Rge: 15-24S-32W
3691 feet from S Section Line, 4071 feet from E Section Line
Lease Name: MAYO C Well #: 1
County: FINNEY Total Vertical Depth: 2705 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2490		WITH 2 SX CMT
PROD	5.5	2581	0	WITH 1000 SX CMT
SURF	8.625	955		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/26/2018 11:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: WES LOGAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: CIBP @ 2490' WITH 2 SX CMT. 12 BBL SPACER 2385'-1860'. 35 SX CMT 1860'-1560'. 11 BBL WATER SPACER 1560'-1100'. 110 SX CMT 1100'-0' FILL ANNULUS

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2018 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 2490' WITH 2 SX CMT. WIRELINE FLUID LEVEL = 2385'. PUMP 12 BBL SPACER 2385'-1900'. PUMP 35 SX CMT 1900'-1560'. PUMP 11 BBL SPACER 1560'-1100'. SHUT DOWN. BLED OFF AIR. PUMP 110 SX CMT 1100'-0'. PUMP 5 SX CMT DOWN THE ANNULUS.

Perfs:


Top	Bot	Thru	Comments
2655	2695		
2557	2560		
2534	2540		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed


5A

(TECHNICIAN)

RECEIVED
MAR - 6 2018
KCC DODGE CITY



INVOICED

APR 26 2018