

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00848-00-01
Spot: SENW Sec/Twnshp/Rge: 16-24S-32W
3930 feet from S Section Line, 2638 feet from E Section Line
Lease Name: MAYO GAS UNIT B Well #: 1
County: FINNEY Total Vertical Depth: 2594 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2060		WITH 2 SX CMT
PROD	5.5	2592	0	WITH 800 SX CMT
SURF	8.625	927		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/26/2018 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: WES LOGAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: CIBP @ 2060' WITH 2 SX CMT. 35 SX CMT 2060'-1700'. 14 BBL SPACER 1700'-1100'. 110 SX CMT 1100'-0'. FILL ANNULUS

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2018 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2060' WITH 2 SX CMT. WIRELINE FLUID LEVEL IS BELOW THE CIBP. 35 SX CMT FROM 2060'-1700'. SPACER FROM 1700'-1300'. SHUT DOWN. ALLOW AIR TO WORKOUT. 145 SX CMT FROM 1300'-0'. PUMP 5 SX CMT DOWN THE ANNULUS. PRESSURE TO 200#.

Perfs:

Top	Bot	Thru	Comments
2563	2572		
2552	2556		
2531	2533		
2518	2524		
2510	2516		
2503	2508		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

INVOICED

APR 26 2018

District: 01

Signed

[Signature]
5A

(TECHNICIAN)

RECEIVED
MAR - 6 2018
KCC DODGE CITY

Form CP-2/3