

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-21936-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 13-14S-15W  
3292 feet from S Section Line, 3641 feet from E Section Line  
Lease Name: NIEDENTHAL - F Well #: 1  
County: RUSSELL Total Vertical Depth: 3305 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3304		150 SX
SURF	8.625	249		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2018 11:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 445-2353

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Holes in casing at 1532'. Squeezed with 200 sx cement.  
Holes in casing at 2510'. Squeezed with 15 sx cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2018 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 250' and 875'. Ran tubing to 3025' and pumped 50 sx cement followed by 75 sx cement w/100 # hulls. Pulled tubing to 2000' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 120 sx cement. Circulated cement to the pit. POOH. Hooked to braden head and pumped 350 # with no fluid moved. Topped off casing with 20 sx cement. Casing standing full. Visibly checked fluid level and it was down less than 25'.

GPS: 38.83641 -098.94141

Perfs:

Top	Bot	Thru	Comments
3183	3187		
3166	3168		
3144	3148		
3043	3047		
3024	3028		
3002	3006		

Remarks: QUALITY CEMENTING TICKET # 514

Plugged through: TBG

INVOICED  
APR 26 2018

District: 04

Signed

*Ray A Dinkel*

Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 16 2018

Form CP-2/3

APR 09 2018

CONSERVATION DIVISION  
WICHITA, KS