

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26708-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 31-11S-19W
1155 feet from S Section Line, 3185 feet from E Section Line
Lease Name: MASSIER "B" Well #: 1-31
County: ELLIS Total Vertical Depth: 3840 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3836		125 SX
SURF	8.625	219		165 SX
T1	2.375	3688		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2018 8:45 AM
Plug Co. License No.: 34275 Plug Co. Name: SCOTT SERVICES LLC
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM CORPORATI Phone: (620) 532-9232

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.
Port collar set at 1486'. Cemented to surface.
PBTD 3790'.
Perforations: 3706' - 3716' and 3678' - 3682'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2018 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Scott Services ran in hole with tubing to 3640'. Pumped 14 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1850' and pumped 194 sx cement w/200 # hulls mixed in to circulate cement to the pit area. Pulled tubing. Topped off 5 1/2" casing with 20' sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 20 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 39.04822 -099.47525

Perfs:

Top	Bot	Thru	Comments
3706	3716		
3678	3682		

INVOICED

APR 26 2018


KCC WICHITA
MAR 16 2018
RECEIVED

Remarks: HURRICANE CEMENTING CO. TICKET # 100888

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

MAR 12 2018

Form CP-2/3