

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-22173-00-00
Spot: NWSWSESW Sec/Twnshp/Rge: 13-30S-33W
514 feet from S Section Line, 1494 feet from W Section Line
Lease Name: NORTH STAPLETON Well #: 13-1
County: HASKELL Total Vertical Depth: 5725 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1694		WITH 620 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/10/2018 2:15 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RODNEY Company: MERIT ENERGY Phone: (972) 628-1558

Proposed Plugging Method: 1ST PLUG AT 1730' WITH 50 SX CMT. 2ND PLUG AT 730' WITH 40 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 02/10/2018 4:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1730' WITH 50 SX CMT. 2ND PLUG AT 730' WITH 40 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BY

Plugged through: DP

INVOICED
APR 26 2018

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
FEB 20 2018
KCC DODGE CITY